

NORTH AND EAST PLANS PANEL

Meeting to be held remotely via Public-i on
Thursday, 9th July, 2020
at 1.30 pm

MEMBERSHIP

Councillors

D Collins
R Grahame
D Jenkins
E Nash
K Ritchie (Chair)
N Sharpe
M Midgley
T Smith
B Anderson

To remotely observe this meeting, please click on the 'View the Webcast' link which will feature on the meeting's webpage (linked below) ahead of the meeting. The webcast will become available at the commencement of the meeting.

https://leeds.public-i.tv/core/portal/webcast_interactive/493013

A G E N D A

Item No	Ward	Item Not Open		Page No
1			APPEALS AGAINST REFUSAL OF INSPECTION OF DOCUMENTS To consider any appeals in accordance with Procedure Rule 15.2 of the Access to Information Rules (in the event of an Appeal the press and public will be excluded) (*In accordance with Procedure Rule 15.2, written notice of an appeal must be received by the Head of Governance Services at least 24 hours before the meeting)	
2			EXEMPT INFORMATION - POSSIBLE EXCLUSION OF THE PRESS AND PUBLIC 1 To highlight reports or appendices which officers have identified as containing exempt information, and where officers consider that the public interest in maintaining the exemption outweighs the public interest in disclosing the information, for the reasons outlined in the report. 2 To consider whether or not to accept the officers recommendation in respect of the above information. 3 If so, to formally pass the following resolution:- RESOLVED – That the press and public be excluded from the meeting during consideration of the following parts of the agenda designated as containing exempt information on the grounds that it is likely, in view of the nature of the business to be transacted or the nature of the proceedings, that if members of the press and public were present there would be disclosure to them of exempt information, as follows:-	

Item No	Ward	Item Not Open		Page No
3	Harewood		LATE ITEMS To identify items which have been admitted to the agenda by the Chair for consideration (The special circumstances shall be specified in the minutes)	5 - 12
4			DECLARATIONS OF DISCLOSABLE PECUNIARY INTERESTS To disclose or draw attention to any disclosable pecuniary interests for the purposes of Section 31 of the Localism Act 2011 and paragraphs 13-16 of the Members' Code of Conduct.	
5			APOLOGIES FOR ABSENCE	
6			MINUTES - 27TH FEBRUARY 2020 To consider and approve the minutes of the North and East Plans Panel meeting held on 27 th February 2020.	
7			19/07228/FU CONSTRUCTION OF A PAIR OF TWO STOREY SEMI-DETACHED DWELLINGS SHERI DENE , ELMWOOD LANE, BARWICK IN ELMET, LEEDS To consider the report of the Chief Planning Officer on an application for the construction of a pair of two storey semi-detached dwellings at Sheri Dene, Elmwood Lane, Barwick in Elmet, Leeds (Report attached)	13 - 34
8			DATE AND TIME OF NEXT MEETING The date and time of next meeting will be Thursday 13 th August 2020 at 1:30pm.	
2				

Item No	Ward	Item Not Open		Page No
a)				
b)				

Third Party Recording

Recording of this meeting is allowed to enable those not present to see or hear the proceedings either as they take place (or later) and to enable the reporting of those proceedings. A copy of the recording protocol is available from the contacts named on the front of this agenda.

Use of Recordings by Third Parties– code of practice

- a) Any published recording should be accompanied by a statement of when and where the recording was made, the context of the discussion that took place, and a clear identification of the main speakers and their role or title.
- b) Those making recordings must not edit the recording in a way that could lead to misinterpretation or misrepresentation of the proceedings or comments made by attendees. In particular there should be no internal editing of published extracts; recordings may start at any point and end at any point but the material between those points must be complete.

NORTH AND EAST PLANS PANEL

THURSDAY, 27TH FEBRUARY, 2020

PRESENT: Councillor K Ritchie in the Chair

Councillors D Collins, R Grahame,
D Jenkins, E Nash, N Sharpe, M Midgley,
T Smith and B Anderson

SITE VISITS

Councillors Collins, Grahame, Jenkins, Nash, Ritchie, Sharpe, Midgley, Smith and Anderson attended the site visits earlier in the day.

74 Appeals Against Refusal of Inspection of Documents

There were no appeals against refusal of documents.

75 Exempt Information - Possible Exclusion of the Press and Public

There were no exempt items.

76 Late Items

There were no late items.

77 Declarations of Disclosable Pecuniary Interests

No declarations of disclosable pecuniary interests were made.

78 Apologies for Absence

There were no apologies.

79 Minutes - 23rd January 2020

RESOLVED – That the minutes of the North and East Plans Panel held on 23rd January 2020, be approved as a correct record.

80 Matters arising

Minute 60 – 19/00867/FU Demolition of existing dwelling and construction of four dwellings, at Greystones, Park Road, Colton. It was noted that in relation to Policies EN1 and EN2 no details had yet been submitted by the applicant.

Minute 70 – 19/05419/FU Demolition of 16 apartments and 6 houses and erection of 85 apartments across two buildings comprising of 51 sheltered housing apartments and 34 general needs apartments with communal car parking and landscaping at land off Queenshill Avenue and Queenshill View, Moortown. It was noted that the Council has 100% of nominations, however this does drop to 60% after a period of time.

It was also noted that officers would feedback in relation to electric changing points for motorcycles for the redraft of the Transport SPD.

Minute 71 19/01665/FU Residential Development of 153 no. of dwellings and associated works at land off Beckhill Approach and Potternewton Lane, Meanwood. The applicant would have to adhere to the 111 agreement in relation to future job opportunities for people from the area.

81 Application 19/07228/FU - Demolition of existing bungalow (retrospective) and erection of a pair of two storey semi-detached dwellings at Sheri Dene, Elmwood Lane, Barwick -in-Elmet, LS15 4JX

The report of the Chief Planning Officer set out an application for the demolition of existing bungalow (retrospective) and erection of a pair of two storey semi-detached dwellings at Sheri-Dene, Elmwood Lane, Barwick-in-Elmet, LS15 4JX.

An objector had submitted further lengthy and detailed representations to the scheme. These had been provided to Members prior to the meeting. The representations had included a heritage statement which officers had not had the opportunity to fully and properly assess.

Therefore, in the interests of robust and safe decision making officers requested that Members agree to defer consideration of the application from the Panel to allow officers to make sure that the objections raised were fully and properly addressed.

RESOLVED – To defer the item for one cycle.

82 Application 19/07601/FU - Change of use and alterations of single dwellinghouse (use class C3) to a House in Multiple Occupation (use class C4) at No. 8 Ecclesburn Street, Richmond Hill, Leeds 9

The report of the Chief Planning Officer set out an application for the change of use and alterations of single dwelling house (use class C3) to a House in Multiple Occupation (HMO) (use Class C4) at no. 8 Ecclesburn Street, Richmond Hill, Leeds 9.

Members had visited the site earlier in the day. Photographs and plans were shown throughout the presentation.

The application had been brought to Plans Panel at the request of Cllr. Khan who was concerned over the removal of this family house, disturbance to residents through increased litter and concerns of anti-social behaviour due to the HMO use. His objections in full were presented at point 15 of the submitted report.

Members were advised that permission was sought to change the use of a house from a single family dwelling to a House in Multiple Occupation, allowing the 5 single bedrooms to be occupied by unrelated persons. Shared facilities would include the basement kitchen and storage space and the ground floor living room.

Members were provided with the following information:

- This is a red brick mid-terrace located in a predominantly residential area;
- Minor alterations were proposed to the external appearance which included:
 - Enlarging the existing rear basement window;
 - Converting ground floor rear door into a window;
 - Rear wall associated with basement staircase to be replaced by a lightweight fence;
 - Bin and bike storage within the rear yard.
- Three of the bedrooms would be en-suite with the two attic bedrooms sharing a bathroom;
- It was noted that all rooms would exceed the national space standards;
- 12 letters of objection and a 32 signature petition had been received. Objection comments were set out at point 14 of the submitted report;
- There is no off-street parking with this property.

Members noted that there were a couple of HMO's located within the area and that one was the subject of enforcement action.

Members suggested that if the proposal went through that 4 bins would be required 2 for waste and 2 for recycling.

A resident of Ecclesburn Street who has lived there for 30 years, attended the meeting and informed the Members that she spoke on behalf of many of the residents who were unable to attend.

The Panel were informed of the following points:

- This community is one that looks after and cares for each other with neighbours offering assistance and checking on each other;
- There have been issues with other HMO's in the area such as drinking, littering and drug users;
- These are family homes with a mix of older people and families with young children;
- No 15 Ecclesburn Road had applied to become a HMO, permission for this had been revoked;

- The resident explained that her husband was terminally ill and she did not wish for him to endure any form of anti-social behaviour or feel that they were being pushed out of the area. She went on to say that her husband, her grandson who lives with her and her community are all precious to her.

Responding to Members questions, the Panel were provided with the following information:

- The demand for these types of properties within this area is big and normally houses are only vacant for approximately 6 months;
- Parking on the street is 'outrageous' and the worry would be that this could increase if new residents have vehicles;
- The community cohesion in the area is very good, very neighbourly and caring;
- The back alley to the properties is not usually full of litter but the visit had taken place the day before the bins were due to be emptied and there are people called 'bin diggers' who rummage through the bins and leave it untidy.

The Agent attended the meeting and informed the Panel of the following points:

- This company refurbishes properties to a high standard to let to professional people;
- He understands the concerns of the residents and wants to work with the residents. He said that his company do reference checks on all their tenants, he could provide video evidence for the properties that he holds and the type of lettings they currently have;
- He said that he had been successful in letting these types of properties in Leeds. He said that if one of their tenants was causing anti-social behaviour they would evict them;
- The properties are inspected every 3 months, cleaning company are employed to ensure that the property is clean and well maintained on a frequent basis;
- The management team would work with the neighbours to ensure that the community were happy with the management of the property.

Responding to questions the agent provided the following information:

- The company manage single lets and HMO's. There are usually no problems as the properties are regularly inspected and this includes monitoring of the bin area;
- The agent had not yet consulted with the residents as he had not been given the opportunity;
- Not all the tenants in a HMO would have a car. The people who live in these types of properties are looking for good transport links to the city;
- Not all young professionals are able to afford a family house;
- Tenancies range from minimum of 6 months, however some residents do stay 3 – 5 years;

- Safety rails would be fitted to the attic staircases, all the rooms would have fire doors as per fire regulations which offer a minimum of 30 minutes protection;
- The kitchen and dining area has been designed to be adequate for 5 people to eat and cook;
- Tenants sign an agreement which also states that they will not have friends or partners staying overnight;
- Internal walls will be lined with acoustic insulation for both heat and sound.

Members were of the view that it was a long way from the attic rooms to the kitchen/dining area, this raised concerns in regards to safety, as some may opt to cook in their room.

Members noted the following points provided by officers responding to questions and comments:

- HMO Licensing guidance is used in relation to room sizes as there is no planning guidance in relation to HMO room sizes. The room sizes for this proposal are compliant with the HMO guidance and in fact the proposed rooms exceed the guidance standards;
- Originally the proposal was for 6 bedrooms. However, proposals are now for 5 bedrooms and a living room. Within the guidance there is no requirement to provide a communal living room;
- HMO Licensing Guidance includes the responsibility of the occupants and fire regulations.

Members' discussions included:

- Amenity space, which included
 - Size of kitchen/diner;
 - Size of outside space;
 - Narrowness of staircases to the attic rooms;
- Community cohesion of the area;
- Whether granting this application might cause a precedent for HMO's in the area;
- Quality of life for any future occupants and for the residents of the street;
- Fire safety issues;
- Off street parking issues;
- Concerns with the proposed design;
- Use and requirement for HMO's.

RESOLVED – Members moved to refuse the application for the following reasons:

- That the development would fail to provide an adequate level of amenity for the occupiers of the HMO;
- That the use of the dwelling as a HMO would harm the amenities of adjacent residents.

Members also resolved to delegate the drafting of the report for reasons of refusal to officers.

83 Application 19/03125/FU - Demolition of existing dwelling and ancillary/domestic outbuildings and replacement with four dwellings, with layout, access and servicing at Farfield House, Wetherby Road, Bramham, LS23 6LH

The report of the Chief Planning Officer set out an application for the demolition of existing dwelling and ancillary/domestic outbuildings and replacement with four dwellings, with layout, access and servicing at Farfield House, Wetherby Road, Bramham, LS23 6LH.

Members had attended a site visit earlier in the day. Photos and plans were shown throughout the presentation.

Members' were informed of the following points:

- Access to the site is not within the Green Belt whereas the rest of the site is;
- The farm was a family dwelling which is now vacant and has fallen into disrepair with windows smashed. The farm has had a number of extensions over the years;
- The plot is close to the village of Bramham and a Public Rights of Way;
- The proposal is for 4 dwellings 2x 2 bed dwellings and 2x 3 bed dwellings of one and a half storeys. The dwellings would be constructed of traditional materials for the area of Bramham;
- The proposed access drive would have two passing bays;
- Each dwelling would have a driveway with parking;
- Sheds to be provided to each rear garden;
- Improved landscaping to the west side of the motorway and north side of fields.

Members' attention was drawn to paragraph 54 of the submitted report which provided a number of positive aspects attached to the development.

There were no objections in relation to this application. However, at the invitation of the Chair the agent and Cllr. Lamb attended the meeting to answer any questions posed by the Panel.

The Panel were provided with the following information in response to their questions and comments:

- This is a low key environment private drive and a third passing place would be rejected. However, consideration could be given to move one of the proposed passing places closer to the bend to assist with visibility;
- Mitigation of noise from nearby major roads will be part of considerations at reserved matters;
- Nature Officer to be consulted on any changes proposed to landscaping; including appropriate development of the area and species to be used. It was noted that the Council has had a trained ecologist officer for a number of years and also tree and landscape

architects who are consulted with in relation to proposed developments;

- A previous scheme on this site had been dismissed. It was noted that there was a marked difference between that scheme and this scheme as presented;

The agent for the development said that Policy EN1 and EN2 would be considered although they are not a requirement as yet. The agent also told the Panel that engagement had taken place with the Parish Council and the Community.

Cllr. Lamb gave his thanks to the agent and the developers for their consultation with the community.

It was noted that the passing places on the access drive would be in place prior to commencement for the use of construction vehicles.

The Planning Officer in his summary informed Members that the Nature Officer would be consulted on any bio-diversity plan submitted and that this would be included as a separate condition. The agent had said that consideration of EN1 and EN2 would be given for a sustainability plan and this would need to be approved.

Members were advised that condition 9 in relation to provision and maintenance of a scheme of sustainable drainage as set out in the submitted report may not be required as the site may drain naturally.

RESOLVED – To grant permission as set out in the submitted report subject to the following amendments:

- Amend condition 9 in respect of the provision of Sustainable Drainage (SD) Management and Maintenance Plan to only require those plans in the event that they are necessary.
- Impose conditions requiring the submission of details in respect of bio-diversity enhancement.

84 Application 18/06186/OT - APPEAL by Mr Patrick Waterhouse against the decision to refuse outline planning permission for a new detached dwelling at 9 Manor Park, Scarcroft, Leeds LS14.

The report of the Chief Planning Officer requested Members to note the appeal decision for planning application 18/06186/OT – Appeal by Mr P Whitehouse against the decision to refuse outline planning permission for a new detached dwelling at 9 Manor Park, Scarcroft, Leeds LS14.

Members were reminded that they had resolved not to accept the officer recommendation and instead resolved to refuse outline planning permission for the reasons set out at paragraph 3 of the submitted report.

Members were advised that the Inspector had upheld their decision to refuse for the following reasons:

- 1) Special character of the area
- 2) Living conditions both in terms of location and proximity of trees to the dwelling. The trees had a preservation order on them.

RESOLVED - To not the content of the report.

85 Date and Time of Next Meeting

The next meeting of North and East Plans Panel will be held on Thursday 9th April 2020, at 1.30pm in Civic Hall, Leeds.



Originator: Steven Wilkinson

Tel: 0113 3787662

Report of the Chief Planning Officer

NORTH AND EAST PLANS PANEL

Date: 9th July 2020

Subject: 19/07228/FU – Erection of a pair of two storey semi-detached dwellings at Sheri Dene, Elmwood Lane, Barwick-in-Elmet, LS15 4JX

APPLICANT

Selby Road Homes

DATE VALID

22 11 2019

TARGET DATE

EOT - 06 03 2020

Electoral Wards Affected:

Harewood

☐ Yes

Ward Members consulted

Specific Implications For:

Equality and Diversity ☐

Community Cohesion ☐

Narrowing the Gap ☐

RECOMMENDATION: GRANT PERMISSION subject to the following conditions:

1. Standard 3 year implementation time limit
2. Compliance with approved drawings
3. Submission of external materials for approval
4. Sample panel of stonework
5. Timber windows and doors (White, cream or natural finish)
6. Portico materials
7. PD rights removed (Classes A-E & means of enclosure)
8. Front wall to be retained and made good
9. South boundary wall to be repaired and made good
10. Submission of drainage scheme
11. EVCP details
12. Vehicle space to be laid out
13. Statement of construction practice
14. Footway crossing
15. Landscaping details and implementation plan
16. Contamination – Phase 2 report (Site Investigation)
17. Contamination - Remediation statement
18. Contamination – Verification reports

- 19. Contamination – Importing soil requirements
- 20. Contamination – Asbestos
- 21. No balconies to flat roofs
- 22. Details of rainwater goods
- 23. Hardstanding to the front to be permeable
- 24. Inclusion of water butts
- 25. Details of scheme to show compliance with Policy H10 – Accessible Housing
- 26. Verification of compliance with Policy H10

INTRODUCTION

1. This application is brought to Plans Panel pursuant to Part 3 2 c Exception 1 (g) of the Constitution as the Chair, in consultation with the Chief Planning Officer, considers that the application should be referred to the relevant Plans Panel for determination because of the significance, impact or sensitivity of the proposal. This consideration is made in light of the ongoing legal proceedings relating to the previous application for the site (19/00882/FU).

BACKGROUND

2. Development of the site was granted planning permission for a similar development in September 2019 under planning application reference 19/00882/FU. However, shortly after the decision was challenged by way of a Judicial Review. The claim sought to challenge the decision on two grounds. Firstly, failure to have regard to the statutory duty within s66(1) of the Planning (Listed Building and Conservation Areas) Act 1990. Secondly, that the Council failed to take into account the impact on residential amenity to the occupiers of Elmwood House and occupiers of 38,40 and 42 Main Street several properties to the rear of the site.
3. In response to the claim the Council has admitted that an error was made regarding ground one. As such the Council has conceded that there is a genuine basis for grounds for Judicial Review which will result in the decision being quashed. The Council and Claimant have agreed a consent order to quash the decision on that basis. At this time proceedings are listed before the High Court for 16 July 2020 because the Interested Party (developer) has not yet agreed the Consent Order. Should the Consent Order be agreed by all three parties then it should be approved by the court without the need for a hearing.
4. The current planning application seeks to obtain planning permission for a similar development. The application has been advertised accordingly and the assessment of the application below includes a full consideration of its impact on the setting of the listed building.

PROPOSAL

5. The proposal relates to the construction of a semi-detached pair of properties which are both of 4 bedrooms. The proposed new dwellings are two storeys in height with a gabled roof design and are a mirror image of one another. The dwellings incorporate a dual flat roofed single storey rear projection which are served by lantern lights. The dwellings will be constructed of natural stone with a natural slate roof.

6. The properties benefit from reasonably large private, rear garden areas and landscaped front garden areas. Both properties incorporate a driveway and off-street parking provision to the front, accessed from Elmwood Lane. In the case of the southern dwelling the existing access to the site is retained. An EVCP point is proposed for each property.

SITE AND SURROUNDINGS

7. A detached bungalow was previously present on the site, however it was demolished in October 2019. At the time of the demolition there was planning permission for the demolition under the grant of planning permission now subject to proceedings. The site is currently vacant and has been prepared for development.
8. The site benefits from a grassed verge between the highway and a front boundary wall. The site is flanked on either side by two, two storey residential dwellings built of stone with red tile roofs, which appear to be of quite recent construction. A former barn which has been considerably altered and is currently in commercial use (electrical contractors and engineering) is located directly adjacent to the site to the north. This building is set back significantly from the highway and the predominant building line. The dwellings to the rear of the site (along Main Street) are situated on a lower land level.
9. A Grade II listed building, known as Elmwood House (44 Main Street) is situated to the south-east of the site. The property is in residential use. The listed building fronts onto Main Street and is positioned in a slightly off-set position to the rear of the site, with the rear of the listed building facing the proposed development. The listed building and grounds are also situated on a lower land level than the development site. A curtilage listed boundary wall which is attached to the listed building extends up the south side boundary of the site up to Elmwood Lane.
10. The site and Elmwood House are situated within the Barwick-in-Elmet conservation area. The boundary of the conservation area runs along Elmwood Lane with the western side of the street falling outside the designated area.
11. The site is situated towards the north-western side of the village of Barwick which has a limited range of services and community facilities, including a parade of shops. The surrounding area is predominantly residential consisting of mainly two storey dwellings of varying design, although the surrounding buildings within the conservation area contain similar detailing elements and are generally of simple form. The palette of external walling and roofing materials is also varied.
12. The site is accessed from Elmwood Lane which is a quiet residential road. The majority of neighbouring properties appear to have off-street parking provision. Elmwood Lane is situated close to Main Street which is a key central route within Barwick-in-Elmet, linking the settlement with surrounding villages.

RELEVANT PLANNING HISTORY

13. 19/00882/FU - Demolition of existing bungalow and erection of a pair of two storey semi-detached dwellings (Granted – 04.09.2019).
14. Application 19/00882/FU is currently subject to the aforementioned ongoing Judicial Review proceedings which are yet to be determined.

HISTORY OF NEGOTIATIONS

15. The following amendments have been negotiated during consideration of the application:
- Increase in the depth of the parapet for the single storey rear projections.
 - Re-siting of the chimneys nearer to the ridgeline.
 - Windows changed from grey to white painted timber.
 - Increased depths of ground floor window head detailing.
 - Improved hard and soft landscaping and confirmation that existing boundary treatments are to be retained.
 - Submission of additional plans further indicating the relationship between the proposal and the adjacent listed building.
16. It should be noted that the previous similar planning application (19/00882/FU) was subject to significant changes following lengthy negotiations prior to permission being granted. The application was originally submitted for two modern detached dwellings. The following amendments were negotiated during the previous application:
- A move from two detached properties to a semi-detached form of dwellings.
 - Relocation of the vehicular access points.
 - Simplification of the detailing elements and fenestration.
 - Retention and refurbishment of the historic front boundary walling.

PUBLIC/LOCAL RESPONSE

17. Representations have been received from 4 neighbouring households, all in objection to the proposed development. An additional letter has also been received from Barwick-in-Elmet Parish Council.
18. The letter from the Parish Council states that it is not considered that the proposal will adversely affect the setting of the listed building. However, the Parish Council is of the view that the new development will overlook properties on Main Street and that the development would represent the over-development of the plot. Concerns are also raised that there could be issues regarding shadows late in the day which would impact on amenity.
19. The letters from the neighbouring residents raise the following concerns:
- Impact on building line
 - Overdevelopment of the plot
 - Traffic / parking concerns
 - Impact on the character of the area.
 - Loss of grass verge
 - Conformity with the Neighbourhood Plan
 - Loss of privacy / overlooking
 - Impact on boundary walling
 - Over-dominance
 - Inadequate landscaping
 - Impact upon the amenity of neighbouring properties

- Impact upon the amenity of future residents
- Harm to the significance of the Grade II listed building at Elmwood House
- Harm to the character and appearance of the conservation area
- Land contamination.
- Principle of development.
- Impact on views.
- Housing delivery (weight)

20. One of the representations included a Heritage Impact Assessment (and supplementary heritage note) produced by the Pegasus Group, which further detailed the aforementioned concerns in relation to the harm to the significance of the Grade II listed building and harm to the character of the conservation area.
21. One of the representations made several comments in relation to the previous panel report (27th February, 2020). These comments have been noted and changes have been made to this updated report where deemed appropriate.

CONSULTATIONS RESPONSES (SUMMARY)

22. Conservation Team – The proposal is to build a pair of houses fronting onto Elmwood Lane set on the same building line as the adjoining houses. The houses would have a simple form, built in stone with a ridge running parallel to the highway like the adjacent houses. The elevational treatment could be called "neo-vernacular" with a dominance of solid over void and regular ordering of small window openings. All in all, siting, form and elevational treatment and materiality will integrate with the neighbouring houses.

(i) Impact of proposal on setting of Elmwood House:

The baseline is a cleared plot. The proposed house will "take its place" in the pattern of residential development fronting both sides of Elmwood Lane within the boundaries of the historic toft and croft boundaries. It will be visible from the garden of Elmwood Lane but offset in views looking west and seen as the pattern of "back line" development along Elmwood Lane. From Carrfield Road, the new houses are in line with existing two storey house which shelter it in views looking north. It will not affect the views of the listed building along Main Street where the new houses will not be seen together with the listed building. The new development will be glimpsed in views through the narrow access between listed building and the house to the north but in this glimpsed and momentary view is not dominating as shown in the recent 3D view submitted by the applicant. The impact of the proposed houses on the setting of Elmwood House and the boundary wall will be neutral.

(ii) Impact of development proposal on Barwick in Elmwood Conservation Area:

The assessment impact on the conservation area has similar considerations to that of the setting of the listed building but with a wider purview taking into account settlement morphology and townscape. The proposed houses will sit within an established pattern of development that sits within the boundaries of the historic toft and crofts (albeit the development site is an amalgamation of several historic plots.) The lateral walls would be kept thereby maintaining the "deep history" of the toft and croft settlement pattern on Main Street which underlies the modern infill. The positive boundary wall onto Elmwood Lane would be punctured to create separate access points for the houses, but the majority of the wall would remain and the visual integrity maintained. Overall, the impact of the development on the

conservation area will be neutral and will therefore preserve the character and appearance of the conservation area.

23. Environmental Studies - On examination of Defra's strategic road maps and the layout and orientation of the proposed dwellings, noise from road traffic is unlikely to be of a level that would require specific measures over and above standard building elements. Therefore in this case we do not require an acoustic assessment to be submitted.
24. Contaminated Land – Further information required in relation to asbestos. Phase 2 Site Investigation report required. Planning conditions suggested.
25. Highways – No objection, subject to conditions.
26. Landscape – Vegetation to front (outside red line) should be retained. Add tree planting to site frontage.
27. Flood Risk Management – No objections, subject to conditions.

PLANNING POLICIES & LEGISLATION

Relevant Legislation

28. Conservation area: Section 72 of the Planning (Listed Buildings and Conservation Areas) Act 1990 states that in the exercise, with respect to any buildings or other land in a conservation area of any functions under the Planning Acts, that special attention shall be had to the desirability of preserving or enhancing the character or appearance of that area.
29. Listed Building: Section 66(1) of the Planning (Listed Buildings and Conservation Areas) Act 1990 states that in considering whether to grant planning permission... for development which affects a listed building or its setting, the local planning authority ...shall have special regard to the desirability of preserving the building or its setting or any features of special architectural or historic interest which it possesses.
30. Section 38(6) of the Planning and Compulsory Purchase Act states that for the purpose of any determination to be made under the Planning Acts, the determination must be made in accordance with the Local plan, unless material considerations indicate otherwise. The Development Plan comprises of the Core Strategy as amended by the Core Strategy Selective Review (2019), Site Allocations Plan (2019), Natural Resources and Waste DPD (2013), Aire Valley Area Action Plan (2017), saved policies of the UDPR (2006) and any made Neighbourhood Plan.

National Policy

National Planning Policy Framework

31. The National Planning Policy Framework (NPPF) sets out the Government's planning policies for England and how these should be applied. It provides a framework within which locally-prepared plans for housing and other development can be produced. Planning law requires that applications for planning permission be determined in accordance with the development plan, unless material

considerations indicate otherwise. The NPPF must be taken into account in preparing the development plan, and is a material consideration in planning decisions.

32. Chapter 5 relates to delivering a sufficient supply of homes. Paragraph 68 highlights that *“Small and medium sized sites can make an important contribution to meeting the housing requirement of an area, and are often built-out relatively quickly”*.
33. Chapter 12 - Achieving well-designed places, states that the creation of high quality buildings and places is fundamental to what the planning and development process should achieve. Good design is a key aspect of sustainable development, creates better places in which to live and work and helps make development acceptable to communities, and that Neighbourhood plans can play an important role in identifying the special qualities of each area and explaining how this should be reflected in development.
34. Paragraph 127 states that:
- “Planning policies and decisions should ensure that developments:*
- a) will function well and add to the overall quality of the area, not just for the short term but over the lifetime of the development;*
 - b) are visually attractive as a result of good architecture, layout and appropriate and effective landscaping;*
 - c) are sympathetic to local character and history, including the surrounding built environment and landscape setting, while not preventing or discouraging appropriate innovation or change (such as increased densities);*
 - d) establish or maintain a strong sense of place, using the arrangement of streets, spaces, building types and materials to create attractive, welcoming and distinctive places to live, work and visit;*
 - e) optimise the potential of the site to accommodate and sustain an appropriate amount and mix of development (including green and other public space) and support local facilities and transport networks; and*
 - f) create places that are safe, inclusive and accessible and which promote health and well-being, with a high standard of amenity for existing and future users⁴⁶; and where crime and disorder, and the fear of crime, do not undermine the quality of life or community cohesion and resilience.”*
35. Paragraph 130 states:
- “Permission should be refused for development of poor design that fails to take the opportunities available for improving the character and quality of an area and the way it functions, taking into account any local design standards or style guides in plans or supplementary planning documents. Conversely, where the design of a development accords with clear expectations in plan policies, design should not be used by the decision-maker as a valid reason to object to development. Local planning authorities should also seek to ensure that the quality of approved development is not materially diminished between permission and completion, as a result of changes being made to the permitted scheme (for example through changes to approved details such as the materials used).”*
36. Paragraphs 189 states:
- “In determining applications, local planning authorities should require an applicant to describe the significance of any heritage assets affected, including any*

contribution made by their setting. The level of detail should be proportionate to the assets' importance and no more than is sufficient to understand the potential impact of the proposal on their significance. As a minimum the relevant historic environment record should have been consulted and the heritage assets assessed using appropriate expertise where necessary. Where a site on which development is proposed includes, or has the potential to include, heritage assets with archaeological interest, local planning authorities should require developers to submit an appropriate desk-based assessment and, where necessary, a field evaluation."

37. Paragraph 190 states:

"Local planning authorities should identify and assess the particular significance of any heritage asset that may be affected by a proposal (including by development affecting the setting of a heritage asset) taking account of the available evidence and any necessary expertise. They should take this into account when considering the impact of a proposal on a heritage asset, to avoid or minimise any conflict between the heritage asset's conservation and any aspect of the proposal."

38. Paragraph 192 states:

"In determining applications, local planning authorities should take account of:

- a) the desirability of sustaining and enhancing the significance of heritage assets and putting them to viable uses consistent with their conservation;*
- b) the positive contribution that conservation of heritage assets can make to sustainable communities including their economic vitality; and*
- c) the desirability of new development making a positive contribution to local character and distinctiveness."*

39. Paragraph 194 states:

"Any harm to, or loss of, the significance of a designated heritage asset (from its alteration or destruction, or from development within its setting), should require clear and convincing justification. Substantial harm to or loss of

- a) grade II listed buildings, or grade II registered parks or gardens, should be exceptional;*
- b) assets of the highest significance, notably scheduled monuments, protected wreck sites, registered battlefields, grade I and II* listed buildings, grade I and II* registered parks and gardens, and World Heritage Sites, should be wholly exceptional."*

40. Paragraph 196 of the NPPF states where a development proposal will lead to less than substantial harm to the significance of a designated heritage asset, this harm should be weighed against the public benefits of the proposal including, where appropriate, securing its optimum viable use.

National Planning Policy Guidance (NPPG)

41. Provides further detailed guidance on a range of planning issues, including in relation to design, determining applications, effective use of land, the historic environment and the use of planning conditions.

Local Policy

Core Strategy, as amended (2019)

42. SP1 - Seeks to concentrate the majority of new development within the main urban areas and ensure that development is appropriate to its context.
H2 - Relates to new housing development on non-allocated sites.
H3 - Density of residential development.
H4 - Housing Mix.
P10 - Seeks to ensure that new development is well designed and respects its context.
P11 - Seeks to ensure that heritage assets are conserved and enhanced.
P12 - Landscape
T2 - Seeks to ensure that new development does not harm highway safety.
G9 - Biodiversity improvements.
EN5 - Managing Flood Risk.
H9 - Minimum Space Standards for new dwellings
H10 - Accessible Housing Standards
EN8 - Electric Vehicle Charging Infrastructure

Natural Resources and Waste DPD (2013):

- | | | |
|-----|------------------|---------------------------------|
| 43. | General Policy 1 | General planning considerations |
| | Water 4 | Development in Flood Risk Areas |
| | Water 6 | Flood Risk Assessments |
| | Water 7 | Surface Water Run Off |
| | Land 1 | Land contamination |

Barwick in Elmet and Scholes Neighbourhood Plan (2017-2028):

44. This plan was 'Made' in 2017 and forms part of the Leeds Development Plan. The policies relevant to this proposal are:
- Policy LE1: Conserving historic character.
Policy BE1: Achieving high quality and sympathetic building design.
Policy BE2: Streets and street scene.
Policy BE4: Drainage and flood prevention
Policy HO2: Type and design of new housing developments.

Saved UDPR (2006) Policies:

45. GP5 - Seeks to ensure that development proposals resolve detailed planning considerations, including amenity.
N25 - Seeks to ensure boundary treatment around sites is designed in a positive manner.
BD5 - The design of new buildings should give regard to both their own amenity and that of their surroundings.
LD1 - Seeks to ensure that development is adequately landscaped.
N19 - All new buildings and extensions within or adjacent to conservation areas should preserve or enhance the character or appearance of the area by ensuring that:

- i. The siting and scale of the building is in harmony with the adjoining buildings and the area as a whole;
- ii. Detailed design of the buildings, including the roofscape is such that the proportions of the parts relate to each other and to adjoining buildings;
- iii. The materials used are appropriate to the environment area and sympathetic to adjoining buildings. Where a local materials policy exists, this should be complied with;
- iv. Careful attention is given to the design and quality of boundary and landscape treatment.

N20 - Demolition or removal of other features which contribute to the character of the Conservation Area and which are subject to planning control, such as trees, boundary walls or railings, will be resisted.

BC7 - Development within conservation areas will normally be required to be in traditional local materials.

Relevant Supplementary Planning Guidance

46.

SPG	Sustainable Urban Drainage
SPD	Street Design Guide
SPD	Leeds Parking
SPG	Neighbourhoods for Living
47. Barwick in Elmet Conservation Area Appraisal and Management Plan (2010): This appraisal and management plan sets out the features that contribute to its distinctiveness and identifies opportunities for its protection and enhancement.

MAIN ISSUES

48. The main issues relating to this development proposal are considered to be:
 - The principle of the development / Housing supply
 - Design and character / Impact on conservation area
 - Impact on setting of listed building
 - Residential Amenity – Neighbouring residents
 - Residential Amenity – Future occupants/Inclusivity
 - Highway Safety
 - Climate emergency

APPRAISAL

The principle of the development / Housing supply

49. The site is situated within the defined urban area of the village of Barwick. The site is a mixture of brownfield and greenfield land, with the brownfield element forming the location of a recently demolished dwelling and the garden areas of the former property being classified as greenfield land.
50. The village of Barwick is characterised as a smaller settlement within the Core Strategy settlement hierarchy. Smaller Settlements are those communities which have a population of at least 1500, a primary school, and a shop or pub. Some but not all Smaller Settlements have a local centre (such as Barwick). Smaller Settlements generally only provide a basic service level. Whilst smaller settlements

are not the priority or focus for housing delivery within the city, they are expected to make a valuable contribution to the city's growth needs. The Core Strategy highlights that Smaller Settlements will contribute to development needs, with the scale of growth having regard to the settlement's size, function and sustainability.

51. The site is not allocated within the adopted Site Allocations Plan. Policy H2 of the Core Strategy states that new housing development on non-allocated land is acceptable in principle providing that specific criteria are met. The proposal will not exceed the capacity of transport, educational and health infrastructure given that it relates to just two dwellings, which will create a very modest infrastructure burden. The proposal does not meet the threshold of 5 dwellings and is consequently not required to comply with the accessibility criteria contained within criterion ii) of Policy H2. Furthermore, the proposal is not situated on land defined as Green Belt, or designated as green space. Policy H2 contains some further criteria which solely relate to the developments on greenfield land. Notwithstanding the fact that the new dwellings will largely be situated on the brownfield elements of the site, these proposal has also be assessed against these criteria. In response, the site is also not considered to have intrinsic value for recreation or nature conservation. Lastly the site is presently untidy whilst also forming a suitable infill plot within an established pattern of development. Consequently, the site is not considered to or make a valuable contribution to the visual, historic or spatial character of the area (further assessed later within the report). Consequently, the proposal is considered to be in general conformity with Policy H2 of the Core Strategy having regard to the fact that the site is part brownfield and situated within a generally sustainable location within the defined settlement hierarchy.
52. Leeds currently benefits from a housing supply in excess of five years. The proposal will provide a very modest contribution to Leeds' housing supply (two units). It will provide family dwellings within a village where limited growth is anticipated over the plan period (albeit Barwick does not have a set housing target).

Design and Character / Impact on Conservation Area

53. Policies within the Leeds development plan and the advice contained within the NPPF seek to promote new development that responds to local character, reflects the identity of local surroundings, and reinforce local distinctiveness. The NPPF states that good design is a key aspect of sustainable development, creates better places in which to live and work and helps make development acceptable to communities. It is therefore fundamental that new development should generate good design and respond to the local character. The NPPF goes on to state that that permission should be refused for development of poor design that fails to take the opportunities available for improving the character and quality of an area and the way it functions, taking into account any local design standards or style guides in plans or supplementary planning documents.
54. Policy P10 of the Leeds Core Strategy deals with design and states that *inter alia* alterations to existing, should be based on a thorough contextual analysis and provide good design that is appropriate to its location, scale and function. Developments should respect and enhance, streets, spaces and buildings according to the particular local distinctiveness and wider setting of the place with the intention of contributing positively to place making, quality of life and wellbeing. Proposals will be supported where they accord with the principles of the size, scale, design and layout of the development and that development is appropriate to its context and respects the character and quality of surrounding buildings; the streets

and spaces that make up the public realm and the wider locality.

55. Policy BE1 of the Barwick in Elmet and Scholes Neighbourhood Plan has similar aims and relates to 'Achieving high quality and sympathetic building design'. It requires any new developments to demonstrate good quality design, responding to and integrating with the surrounding built character and landscape, taking account of key design principles such as scale and character. New development should wherever possible should draw upon and be inspired by the best design features of the conservation area. The policy also requires local or sympathetic building materials and for developments within conservation areas to conserve or include detailing features such as sills, lintels, chimney stacks and porches.
56. In addition, Policy HO2 of the Neighbourhood Plan relates to 'type and design of new housing developments' and requires new developments to reflect their surroundings and be similar in terms of density, footprint, separation, scale and bulk. The policy also states that support will be given to developments which:
- provide one and two storey housing in keeping with the rest of the built form,
 - provide new housing on smaller sites within the established settlements which assimilate into the existing community,
 - Re-use redundant buildings
 - Re-use previously developed land before greenfield sites
 - Reflect the existing built form with garden and backland development supported only where it does not result in housing density which is out of keeping with the locality.
 - Provide appropriate landscaping.
57. The proposal lies within the Barwick in Elmet Conservation Area. Section 72(1) of the Planning (Listed Buildings and Conservation Areas) Act 1990 requires the LPA to pay special attention to the desirability of preserving or enhancing the character or appearance of a conservation area when granting planning permission. Development Plan policies, and in particular Policy N19, also seek to conserve the historic character of designated areas. The NPPF is clear that any harm to a designated heritage asset, should require clear and convincing justification.
58. Policy LE1 of the Neighbourhood Plan relates to 'Conserving historic character' and requires development proposals to be sensitively designed to consider the rural and historical character of the area and pay due regard to the importance of non-designated historic assets.
59. The proposed dwellings will be constructed of natural stone and slate which are common and traditional building materials both within the immediate context and the wider conservation area. It is noted that both adjacent dwellings incorporate red tile roofs. However, the presence of red tile roofs within this part of the conservation area is limited and such roofs when found are generally scattered around, usually in clusters of no greater than two dwellings. Within this context the use of slate is appropriate and supported.
60. The proposed dwellings are two storey in scale and incorporate a gabled roof form, which is typical of the surrounding conservation area context. Whilst the new dwellings will be semi-detached properties, the form and scale of the pair of dwellings will be similar to the adjacent detached units. Furthermore, the siting and orientation of the dwellings is considered to be sympathetic, with the new dwellings positively addressing Elmwood Lane, whilst retaining a suitable set back from the highway, creating a consistent stepped building line with the adjacent dwellings.

The proposed dwellings will be two storey in scale, however the semi-detached pair are set away from both site boundaries of the plot, ensuring that adequate and characteristic spatial relief between the dwellings is retained. The staggered nature of the building line further helps to create visual breaks and reduces the potential massing of the development.

61. The design of the new dwellings has taken inspiration from positive features from neighbouring dwellings within the conservation area. A key characteristic of the neighbouring buildings is their simple elevations (especially at first floor level) and uncluttered roofs. The proposed dwellings respect this prevailing character and incorporate simple elevations which feature characteristic heads and cills detail, corbels, timber openings and a window design which takes inspiration from the neighbouring terrace to the south, which is identified as a positive building within the associated conservation area appraisal. The properties incorporate a modest canopy (portico) above the front doors. Small single storey front additions are a feature of the neighbouring properties and the proposed design is considered suitable and not out of keeping with the street scene. The proposed rear orangeries are of sympathetic design and scale and will be largely screened from public views. The proposal also incorporates chimneys on the front facing roof slope. Chimneys are a common feature within the conservation area and provide important vertical articulation. The neighbouring chimneys are of varying design and siting. A notable attention to detail has also been applied to the smaller elements of the scheme, such as the EVCP points, which take the form of a screened modest timber box and have been sited to reduce their prominence, to ensure that they assimilate appropriately within the surrounding context.
62. Furthermore, the existing site is currently of an untidy appearance with very little vegetation. The proposal includes the creation of landscaped front and rear garden areas which will tie in with the salient character of the area and will be an improvement on the current situation.
63. Overall in general design terms the proposal is considered to be sympathetic to the existing streetscene. In particular, Policy BE1 of the Neighbourhood Plan supports such developments which draw upon and are inspired by the best design features of the conservation area. Policy HO2 of the Neighbourhood Plan also expressly supports developments which amongst other things are one or two storey in scale, provide new housing on smaller sites and re-use brownfield land, all of which the proposal achieves.
64. In terms of the site's contribution to the Conservation area the Barwick-in-Elmet Conservation Area Appraisal and Management Plan provides an assessment of the special architectural and historic character of the conservation area and guidance and policies to maintain that special character taking into account settlement form, activity and grain, key views and architectural character. Under 'Settlement form', it refers to the village's "medieval linear form, with Elmwood Lane marking the rear of the former toft plots" and says that while the linear strips of former crofts to the west have been largely obscured by late 20th century development, "the backland character of Elmwood Lane is an important feature in the settlement". In that the listed building is within the conservation area there is a great deal of overlap between the setting of the listed building and the special architectural and historic interest of the conservation area, with the application site lying adjacent to Elmwood House. The Barwick-in-Elmet Conservation Area Appraisal recognises the importance of toft and croft layout which it says were laid out in a standardized form, "with regular-sized house plots (tofts) and long narrow garden plots (crofts) lining the west side of a new street running south". The application site is an

amalgamation of two crofts subdivided to create a separate rear plot in the 19th century and then developed in the late 20th century when the previous bungalow was built. The spatial frame of the plot is defined by tall side walls extending from Main Street and returning along Elmwood Lane (although reduced in height and partially rebuilt in brick) demarcating the rear of the historic toft and croft. The site is currently fallow following the recent demolition of the bungalow and appears as an anomaly given the established pattern along Elmwood Lane of modern frontage residential development.

65. The proposed houses will sit within an established pattern of development that sits within the boundaries of the historic toft and crofts (albeit the development site is an amalgamation of several historic plots.) The lateral walls would be kept thereby maintaining the "deep history" of the toft and croft settlement pattern on Main Street which underlies the modern infill.
66. A key aspect of the conservation interest at the site is the historic stone front boundary wall which matches the adjacent properties and runs up the east side of Elmwood Lane. The front wall of the site has previously been unsympathetically increased in height with the addition of some red brickwork in the past. The proposal includes retaining the majority of the stone wall and refurbishing it, by removing the brick elements and making good the stone built areas, where necessary. The positive boundary wall onto Elmwood Lane would be punctured to create a new access points for one of the houses, but the majority of the wall would remain and the visual integrity maintained. The curtilage listed wall which runs up the east part of the site will also be retained (repaired where necessary), and exposed as part of the new development. Furthermore, the proposal will also retain a large amount of the existing front grass verge which is a positive feature of the streetscene and conservation area.
67. In light of all of the above factors it is concluded that the design and detailing of the proposal is considered to be sympathetic and in keeping with the character and appearance of the existing streetscene. Overall, the impact of the development on the conservation area will be neutral and will therefore preserve the character and appearance of the conservation area. Accordingly, the proposal would comply with policies P10 and P11 of the Core Strategy, policies GP5, N19, BC7, LD1 and N20 of the UDPR and policies LE1, BE1 and HO2 of the Neighbourhood Plan and would also not conflict with the guidance set out in the NPPF. As such, the legal duty under Section 72 of the Planning (Listed Buildings and Conservation Areas) Act 1990 is discharged in regards to this appraisal.

Setting of the Listed Building

68. A Grade II listed building, known as Elmwood House (44 Main Street) is situated to the south-east of the site. It is an early 19th century house fronting straight onto Main Street. It has architectural value as a well-preserved example of a late Georgian house with carefully controlled proportions and arrangement of windows and a timber doorcase with a modillioned cornice which extends to the interior with its double pile room layout, staircase and panelled doors. It has historical value as illustration of the development of polite architectural style in contrast to the surrounding vernacular buildings.
69. The rear elevation of the building faces the site. The proposal is considered to be within the setting of the listed building. Section 66 (1) of the Planning (Listed Building and Conservation Area) Act 1990 requires that where a development affects a listed building or its setting, special regard should be given to the

desirability of preserving the building or its setting, or any features of special architectural or historic interest which it possesses. Further paragraph 194 NPPF states that any harm to, or loss of, the significance of a designated heritage asset (from its alteration or destruction, or from development within its setting), should require clear and convincing justification.

70. The council's Conservation and Design Team's lead officer has given in depth guidance in respect of this proposal and that advice in so far as it relates to the setting of the listed building is set out in the following paragraphs.
71. Heritage England advice note GPA3 (second edition) 'The Setting of Heritage' Assets provides advice on the setting of heritage assets. Setting is as defined in the NPPF and comprises the surroundings in which a heritage asset is experienced. Elements of a setting can make positive or negative contributions to the significance of an asset and affect the ways in which it is experienced. Historic England states that setting does not have a boundary and what comprises an asset's setting may change as the asset and its surrounding evolve. Setting can be extensive and particularly in urban areas or extensive landscapes can overlap with other assets. The contribution of setting to the significance of an asset is often expressed by reference to views and the GPA in paragraph 11 identifies those views such as those that were designed or those that were intended, that contribute to understanding the significance of assets. In assessing the extent to which setting may contribute to the significance of an asset (step 2), Historic England sets out a number of attributes and these include the assets surroundings and the experience of the asset.
72. Elmwood House's wider setting is the village of Barwick-in-Elmet, particularly its position in a continuously built up linear street frontage to the principal street. The continuous frontage is a function of a historical plot division consisting of a narrow frontage to a long strip of land of land running back from Main Street to Elmwood Lane, known as a "toft and croft", betraying the medieval (probably planned) origins of the settlement. The spatial pattern is reinforced by boundary walls that run back from the frontage to Elmwood Lane. The setting is appreciated from Main Street, Carrfield Road and Elmwood Lane, and could therefore be said to be relatively confined. The glimpsed view between the gable of the listed building and the building to the north from Main Street is important as it shows the depth of plots, although views to Elmwood Lane showing the original extent of the historic toft and crofts cannot be readily appreciated because of existing development on Elmwood Lane. Views from Carrfield Road and Elmwood Lane show the parallel pattern of historic and more modern development within historic toft boundaries defined by stone walls stretching back from Main Street. In this way, it is possible to read co-existing phases of the medieval tofts and crofts defined by stone boundary walls overlaid by a much more modern speculative infill.
73. The baseline is a cleared plot following the demolition of the bungalow. The Pegasus heritage's analysis, the removal of buildings from the plot has not restored the development site to the historical toft and croft which map evidence shows was subdivided in the 19th century, the boundary of which is today is marked by a high hedge. The separate ownership has eroded visual evidence of a shared curtilage and functional dependency of a toft and croft but the historical spatial unit can still be read due to the lateral boundary walls. In effect, the proposed houses will "take their place" in the pattern of residential development fronting both sides of Elmwood Lane within the boundaries of the historic toft and croft boundaries. They will be visible from the garden of Elmwood Lane but offset in views looking west and seen as the pattern of "back line" development along Elmwood Lane. From

Carrfield Road, the new houses are “in check” with existing two storey house which shelter it in views looking north. It will not affect the views of the listed building along Main Street where the new houses will not be seen together with the listed building. The new development will be glimpsed in views through the narrow access between listed building and the house to the north but in this glimpsed and momentary view is not dominating as shown in the recent 3D view submitted by the applicant.

74. The development plot as a cleared site contributes positively setting of the Elmwood House listed building. This derives from the boundary walls stretching between Main Street and Elmwood Lane defining the historical toft and croft rather than use which in common with the adjoining tofts and crofts is the result of the subdivision and residential infilling. The development proposal will maintain the boundary walls and reinstate “back to-back pattern” of development between Main Street and Elmwood Lane. The analysis of views shows that new houses will not dominate the listed building in views from the garden and surrounding streets. In this context, the proposed development is considered to do no harm to the setting of the listed building and can therefore be said to preserve its special interest.

Residential Amenity – Neighbouring residents

75. Core Strategy Policy P10 and saved UDP policy GP5 note that development should protect amenity whilst policy BD5 notes that “all new buildings should be designed with consideration given to both their own amenity and that of their surroundings”.
76. The proposed dwellings will be situated a sufficient distance from neighbouring properties and main garden areas to prevent a significantly harmful overshadowing impact or loss of light to neighbouring windows or garden areas. Similarly these distances will prevent any undue loss of outlook from neighbouring properties. Notably neither of the adjacent properties, to either side of the application site, contain any main windows within their side elevations which face the proposal. The nearest building to the north-east is also commercial in nature containing limited openings. To the south is a dwelling and the proposed dwellings are sited so that they project beyond the rear of that property. However, there is a reasonable degree of separation between the dwellings and that, in combination with the orientation, means that the new development should not appear overbearing or result in any loss of sunlight or cause shadowing to the property to the south. It is noted that the dwelling to the south has a large detached outbuilding sited adjacent to the common boundary with the application site. The buildings to the rear are located on a lower land level. However, the two storey bulk of the development will be situated over 18 metres from the rear boundary and approximately 28 metres at its closest point to the rear of 42 Main Street which is directly to the rear of the application site. These distances are considered to be more than adequate, even when allowing additional distance to compensate for the change in land levels to prevent any undue overshadowing or overdominance.
77. The proposed two storey bulk of the new dwellings will also be situated over 23 metres, at its closest point, to the adjacent listed building (to the rear), which is considered more than adequate even when taking the land level differences into consideration to prevent any significant overdominance. Furthermore, the proposal will be situated to the north-west of the listed building, consequently it will not result in any undue overshadowing given the sun’s path. The two-storey element of the proposed dwellings will be situated approximately 4.8 metres from the listed building’s garden area at its nearest point. This distance is considered acceptable and the dwellings will not unduly dominate the neighbouring private amenity space,

even when compensating for the land level differences, especially given its offset relation to the listed building's garden area. The proposed orangery elements of the proposal will be situated approximately 4.3 metres from the listed building's garden. This distance is considered to be adequate, given the single storey nature of these elements and the existing substantial stone wall. Overall it is considered that the proposal will not be unduly detrimental to the amenity of any neighbouring properties in terms of loss of light, over-dominance or loss of outlook.

78. Given the separation distances highlighted above it is also considered that the proposal will not result in any undue loss of privacy to the rear, even taking into account the land level differences. The distances to the properties to the rear of over 23 to 30 metres from the first floor windows exceed the recommended minimum distance of 21 metres contained within Neighbourhood for Living. Even considering the land level changes it is considered that this distance is more than adequate to prevent any undue loss of privacy. The rear windows within the proposed dwellings will directly face towards the rear of the site. The adjacent listed building is situated in an offset position to the east/south-east of the windows. As such it is considered that no undue overlooking of adjacent listed building or private amenity space will occur. Furthermore, the proposed first floor windows will be situated over 23 metres from the listed building's rear elevation, which contains a secondary window (which is currently being used as a study), as its nearest point. Given these distances and spatial relationship with the neighbouring listed building it is considered that no undue loss of privacy will occur to the neighbouring occupants.
79. Adequate separation distances (over 21 metres) are also provided to the neighbouring dwellings to the front. It is noted that the proposed dwellings contain a kitchen window within their side elevations. However, this opening is not considered to cause any significant overlooking concerns, given that the southern window will be screened by the existing high boundary wall which will be retained. The window within the north elevation will also only overlook the car parking area for the adjacent commercial area. The presence of secondary/tertiary windows within side elevations at ground floor level can also assist with security and surveillance. It is therefore considered that the proposal will not be unduly detrimental to the privacy of any neighbouring occupants.
80. As such it is considered that the proposal will not significantly harm neighbouring amenity in any of the above respects.

Residential Amenity/inclusivity – Future occupants

81. The NPPF (paragraph 127), states decisions should ensure that developments create a "high standard of amenity for existing and future users". New residential development should look to provide a good level of amenity for future occupiers. This includes providing living accommodation which is of an appropriate size, offers appropriate outlook, gives good daylight and sunlight penetration, protects privacy and ensures an appropriate juxtaposition of rooms both within a property and with neighbouring properties to prevent general noise and disturbance issues. This also includes providing good quality outdoor amenity areas for the enjoyment of occupiers.
82. The proposed new dwellings are reasonably large in size and meet the minimum space standard requirements contained within the Core Strategy (as amended 2019). The dwellings are designed so that they will receive adequate sunlight, outlook and will maintain suitable levels of privacy between dwellings. The

dwellings also benefit from significant rear private garden areas. The neighbouring properties to the rear are located on a lower land level. Given the distances and relationship between the proposal and the neighbouring properties to the rear and east/south-east it is considered that the occupants of the new dwelling will benefit from an adequate level of privacy. Overall it is considered that the proposal provides a good standard of amenity for future occupants.

83. Policy H.10, the delivery of accessible housing, requires the provision of one unit to meet part M4(2) of the Building Regulations. Specifically that it is 'accessible and adaptable'. Both units are capable of meeting the requirements and planning conditions are suggested to secure and deliver compliance with Policy H.10.

Highway Safety

84. Core Strategy policy T2 and saved UDP policy GP5 note that development proposals must resolve detailed planning considerations and should seek to maximise highway safety. This means that the applicants must demonstrate that the development can achieve safe access and will not overburden the capacity of existing infrastructure. As outlined within the spatial policies of the Core Strategy it is also expected that development is sited within sustainable locations and meets the accessibility criteria of the Core Strategy. In addition Policy BE2 of the Neighbourhood Plan relates to 'Streets and Streetscene'. The policy seeks to improve connections from developments, whilst also requiring that adequate off-street parking is provided within sites
85. The proposed dwellings both incorporate hardstanding to the front which is large enough to accommodate the required two off-street parking spaces per dwelling. Consequently, the proposal is considered to provide adequate off-street parking provision and is unlikely to significantly increase the need for on-street parking within the locality. The southern dwelling will retain the existing vehicular access. A new access is to be provided for the northern dwelling. This access is set away from the neighboring accesses and achieves suitable visibility splays (2.4 x 43m), given the context of Elmwood Lane which is a generally quiet residential road. The proposal will create two dwellings. The additional traffic impact of two additional dwellings will be negligible. Consequently, the proposal is not considered to be detrimental to highway safety.

Climate Emergency

86. The proposal relates to a minor development and does not meet the thresholds for compliance with Core Strategy policies EN1 (Climate Change – Carbon Dioxide Reduction) and EN2 (Sustainable Design and Construction). The proposal does however relate to the re-development and efficient use of a part brownfield site located within an established urban area within the settlement hierarchy. The development also incorporates two EVCP's, water butts and the hardstanding to the front will be permeable (secured by planning condition). Furthermore, the proposal will result in a net increase in vegetation and landscaping at the site in particular in relation to new tree and hedge planting (given that the baseline for assessment is an untidy site generally devoid of landscaping), in line with Policy G9 of the Core Strategy which will have biodiversity and carbon capture benefits. Overall, the proposal is not considered to raise any notable concerns in relation to the Council's Climate Emergency declaration.

REPRESENTATIONS

87. As previously outlined eight letters of representation have been received, all in objection to the proposed development. The main issues raised are responded to below:
- Impact on building line – There is no building line as such along this part of Elmwood Lane, given sites location near a curve in the road the building line is staggered and inconsistent. Nevertheless, the proposed dwellings will be sited and orientated in a sympathetic manner, and will retain a significant setback from the highway to the front. Consequently, no conflict is found in this regard.
 - Overdevelopment of the plot – The density of the proposed development and spatial separation is considered to be appropriate given the surrounding context.
 - Traffic / Parking concerns – This issue is covered appropriately within the appraisal above with no significant harm identified.
 - Impact on the character of the area - This issue is covered appropriately within the appraisal above with no significant harm identified.
 - Loss of grass verge – The majority of the existing grass verge will be retained, with only a small section lost to provide access to the second dwelling. The loss of a small part of the verge is not considered to be significant.
 - Conformity with the Neighbourhood Plan – The proposal has been assessed against the relevant requirements of the Barwick and Scholes neighbourhood Plan within the appraisal above.
 - Loss of Privacy / overlooking- This issue is covered appropriately within the appraisal above
 - Impact on boundary walling – The proposal will retain and make good the boundary walls to the sides of the site. The development will also enhance the existing front boundary wall by removing the incongruous brick element, whilst the visual integrity of the wall is still considered to be maintained following the creation of a second vehicular access. Consequently, no harm is identified in this regard.
 - Over-dominance - This issue is covered appropriately within the appraisal above.
 - Inadequate landscaping – The revised plans indicate that the proposal will provide a net increase in vegetation and landscaping at the site. The detailed landscaping works will be subject to a planning condition requiring the further approval of details.
 - Impact upon the amenity of neighbouring properties - This issue is covered appropriately within the appraisal above. .
 - Impact upon the amenity of future residents - This issue is covered appropriately within the appraisal above.


- Harm to the significance of the Grade II listed building at Elmwood House - This issue is covered appropriately within the appraisal above. .
- Harm to the character and appearance of the conservation area - This issue is covered appropriately within the appraisal above.
- Land contamination – It is noted that the previous bungalow has already been demolished. However it is considered that any land contamination issues on the site can adequately be dealt with via the use of planning conditions.
- Principle of development - This issue is covered appropriately within the appraisal above.
- Impact on Views - Loss of views in the general sense is not considered to be material planning consideration. In general planning is concerned with land use in the public interest, as opposed to private interests. Notwithstanding this, the impact on outlook and conservation area views has been considered in the appraisal above.
- Housing delivery (weight) – The proposal will provide two dwellings. The delivery of appropriate small scale housing sites (windfall) is very important to Leeds' overall housing delivery and is expressly supported within the Barwick and Scholes Neighbourhood Plan. Notwithstanding this, the proposal is considered to comply with the Development Plan and the developments contribution towards housing delivery has not been given undue or defining weight in this instance.

CONCLUSION

88. In light of the above, it is concluded that the proposal would preserve the character and appearance of the conservation area, and would not harm the setting of the Elmwood House and the curtilage listed wall, preserving its special interest. It is also considered that there would not be undue harm to nearby residents through overlooking, dominance and overlooking, and there would be no material harm to the local highway network, or any other material harm. The proposal is therefore considered to accord with up-to-date planning policies within the Development Plan with no material considerations to indicate otherwise. In accordance with guidance within the NPPF and the local planning policy guidance and legal tests set out above, it is recommended that the application be approved subject to conditions.

Background Papers:

Application files: 19/07228/FU
 Certificate of ownership: Certificate A signed by agent



NORTH AND EAST PLANS PANEL

© Crown copyright and database rights 2020 Ordnance Survey 100019567

PRODUCED BY CITY DEVELOPMENT, GIS MAPPING & DATA TEAM, LEEDS CITY COUNCIL

Page 33

SCALE : 1/1500




S:\000 Projects\3092 Elmwood Lane, Barwick in Elmet\0.00 Drawings\0.01 Project Drawings\3092 Elmwood Lane - Site 005 with topog.rvt

Copyright of this drawing remains the sole property of Den Architecture Ltd unless otherwise assigned in writing. Do not scale from this drawing. Figured dimensions are to be worked in all cases with any discrepancies reported to Den Architecture Ltd prior to commencement of any work.

Northpoint:

Rev	Date	Amendments	By	Chkd
A	10/04/19	Landscape & Highways amended to Sustainability Landscape & Highway team comments	SC	DJR
B	05/07/19	Revised to Highways Comments	SC	ST
C	12/07/19	Revised to Planners Comments	SC	DJR
D	26/07/19	Layout revised following planners comments	ST	DJR
E	19/08/19	Layout revised following planners comments	ST	DJR
F	07/11/19	Site Section added. Site layout updated.	ST	DJR
G	07/11/19	Site Section Amended	ST	DJR
H	21/01/19	Site Layout amended to Suit Planners Comments	ST	DJR

Note:
Vehicle Charging point - IP65 rated domestic socket 13amp socket, directly wired to the consumer unit with 32 amp cable to an appropriate RCD.



den

architecture

8 Wharf Street, Leeds, LS2 7EQ
23 Hanover Square, London, W1S 1JB

T: 0844 844 0070
F: 0844 844 0071
info@den.uk.com
www.den.uk.com

Project: Residential Development Elmwood Lane, Barwick in Elmet				
Client: Selby Road Homes				
Dwg Title: Proposed Site Layout				
Date: Jan 19	Scale: As indicated	Size: A1	Drawn: SC	Checked: DJR
Project No: 3092	Dwg No: 100	Rev: H	Status: Planning	